

09

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division,
SCHDULE-B

Name of Work: Improvements and Asphalting to Aswathkatte Main road Basaveshwara road and Other roads in Mallasandra, Ward No.13, SSD,


Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed. complete as per Specifications.	Cum	419.35	110.24	Rupees One Hundred Ten and Twenty Four Paise Only
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per Specifications.	Cum	55.80	1059.48	Rupees One Thousand Fifty Nine and Forty Eight Paise Only
3	Providing and applying primer coat with bitumen emulsion on prepared surface of granular Base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means complete as per specifications.	Sqm	930.00	39.64	Rupees Thirty Nine and Sixty Four Paise Only
4	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	15689.00	2.38	Rupees Two and Thirty Seven Paise Only
5	Tack Coat:- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom complete as per specifications.	Sqm	15500.00	10.80	Rupees Ten and Eighty Paise Only


Technical Manager (TM-2)
Signature of the Contractor
SMBL, Dasarahalli Zone, Bangalore


Executive Engineer

6	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No. 500.8 complete in all respects as per specifications.	Cum	390.35	8829.00	Rupees Eight Thousand Eight Hundred Twenty Nine Only
7	Carriage of mixed materials 10 kms complete as per Specifications.	Cum	390.00	56.70	Rupees Fifty Six and Seventy Paise Only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 2 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading. complete as per Specifications.	Cum	49.30	70.33	Rupees Seventy and Thirty Three Paise Only

Signature of the Contractor
Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore


 Executive Engineer,
 Dasarahalli Division,

